

SSS019-P07

会場:コンベンションホール

時間: 5月23日17:15-18:45

## IODP319研究航海のライザー掘削孔におけるワイヤーライン検層の計画と実施

### Planning and operation of wireline logging in riser hole in IODP Exp319

真田 佳典<sup>1\*</sup>, モー キョー スー<sup>1</sup>, 木戸ゆかり<sup>1</sup>, 川村善久<sup>2</sup>, 江口暢久<sup>1</sup>, ショーン トシコ<sup>1</sup>, 高橋共馬<sup>1</sup>, 日野亮太<sup>3</sup>, 松田繁美<sup>1</sup>, 倉本真一<sup>1</sup>, 東 亘<sup>1</sup>, IODP319研究航海乗船研究者<sup>4</sup>

Yoshinori Sanada<sup>1\*</sup>, Moe kyaw Thu<sup>1</sup>, Yukari Kido<sup>1</sup>, Yoshihisa Kawamura<sup>2</sup>, Nobuhisa Eguchi<sup>1</sup>, Sean Toczko<sup>1</sup>, Kyoma Takahashi<sup>1</sup>, Ryota Hino<sup>3</sup>, Shigemi Matsuda<sup>1</sup>, Shin'ichi Kuramoto<sup>1</sup>, Wataru Azuma<sup>1</sup>, IODP Expedition 319 Science Party<sup>4</sup>

<sup>1</sup> (独) 海洋研究開発機構, <sup>2</sup>IODP-MI, <sup>3</sup>東北大学, <sup>4</sup>IODP319研究航海乗船研究者

<sup>1</sup>JAMSTEC, <sup>2</sup>IODP-MI, <sup>3</sup>Tohoku University, <sup>4</sup>IODP Expedition 319 Science Party

The first riser hole was drilled by JAMSTEC D/V Chikyū in IODP Expedition 319 in 2009, and wireline logging was conducted. This is the first drilling with riser system and well logging in the riser hole in IODP history. Well logging with new tools, downhole stress measurement, and two-ship long offset walkaway VSP (Vertical Seismic Profiling) were conducted. The hole is drilled at TD 1603.7mbsf under 2054m sea water. Cores sampling, cuttings analysis, gas monitoring were conducted as well. The expedition 319 is one of series of NanTroSEIZE Project, which goal is to reveal earthquake mechanism in Nankai trough seismogenic zone in Japan. This presentation reports the operational planning and review.

IODP standard wireline logging items: natural gamma-ray, resistivity, density, porosity, sonic velocity, resistivity image were measured. The advantages of riser dilled hole against riserless drilled hole for wireline logging are 1) stable hole condition, 2) accurate environmental correction by controlled drilling mud, and 3) large variation of tool selection because of regular hole size instead of slim hole by conventional IODP riser drilling. A couple of new tools were used for new measurement and improvement of the data quality. The Sonic Scanner (trademark of Schlumberger) successfully measured compressional and shear velocity in very low velocities at the soft sediment, where it has been difficult to measure them with conventional DSI tool. The stress and pore pressure in the borehole were measured with the wireline logging tool, (Schlumberger MDT). The single probe tool enable to measure temporal formation fluid pressure. The double packer tool enable to fracture test by sealing and pumping in the borehole. These in-situ measurement and stress experiment data are very important to understand physical properties and mechanism of fault zone.

Super long offset walkaway VSP was conducted to reveal detail subsurface structure and velocity distribution. The 16 sets of the no planned 3-C geophone are clumped with 15m spacing at ~1300-1600mbsf in the cased C0009 hole by Chikyū. Eight OBS (Ocean Bottom Seismometer)s deployed at the seafloor. JAMSTEC R/V Kairei shot along 53km line (maximum offset from the hole is ~30 km) and round 3.5km circle with 16-array tuned air-gun. Zero-offset VSP was conducted to measure velocity and create seismogram along the well as well. Using high resolution data obtained from the equipment, detailed structural interpretation, anisotropy analysis, and shear velocity analysis are being carried out.

Riser drilling takes not only operational advantages such as deeper and safety hole, but also scientific advantage such as increasing measurement items which has never done in riserless

drilling and improving data quality. It enlarges the options to approach new discovery and Science.

キーワード: 検層, ライザー掘削, 南海トラフ, IODP

Keywords: well logging, riser drilling, Nankai trough, IODP